

INFORMATION NEED FOR TROUP COUNTY SHERIFF'S OFFICE FENCE PROJECT

Areas	Total Amount of Post					Extension Arms needed	Total Fence Length to include the gates. We will need 3 runs of 30" Razor Ribbon to include the Razor Ribbon on the 45 degree post arms.	Fence needs 5 runs of 30" Razor Ribbon to include the Razor Ribbon on the 45 degree post arms.	Total Razor Ribbon Needed	Fence Average Height	Drive Thru Gate	Walk Thru Gate
	2 1/2"	3"	4"	2" Gate post	Total							
Pod A	31	7	5	3	46	46	392' a row	27' a row	1,311'	12'	1 - 12' wide	1 - 5' Wide
Pod B	37	6	5	2	50	50	472' a row	N/A	1,416'	12'	1 - 12' wide	N/A
Pod C	0	26	7	0	33	33	272'	N/A	816'	12'	1 - 12' wide	1 - 5' Wide
Total	68	39	17	5	129	129			3,543'			

Notes

The second Row
of existing razor
wire needs to be
lifted up around
6 inches.